## <u>SHEET INDEX</u>

- TI.O COVER
- TI.I PROJECT NOTES
- AI.O SITE PLAN
- SI.O MOUNTING & RACKING METHOD
- EI.O ELECTRICAL LAYOUT
- EI.2 CONSTRUCTION DETAILS
- E2.0 ELECTRICAL DIAGRAM
- DI.O EQUIPMENT DATA SHEETS

## GOVERNING CODES & STANDARDS

2016 CA ELECTRICAL CODE: § 110, 240, 250, 690, 705 2016 CA BUILDING CODE: § 1507.17, 1510.7, 3111 2016 CA FIRE CODE: § 605.11 UNDERWRITERS LABORATORIES (UL) STANDARDS OSHA 29 CFR 1910.269

# PROJECT DESCRIPTION

THIS 2.344 MWSTC, ROOF MOUNTED PHOTOVOLTAIC (PV) SYSTEM IS TO BE INSTALLED AT THE WAREHOUSE IN LOS ANGELES, CALIFORNIA. THE ENERGY PRODUCED BY THE PV SYSTEM SHALL BE INTERCONNECTED WITH THE UTILITY GRID THROUGH THE ON-SITE ELECTRICAL EQUIPMENT VIA A NEW SUPPLY-SIDE SERVICE CONNECTION. THIS PROJECT DOES NOT INCLUDE ENERGY STORAGE BATTERIES.

## COMPONENTS LIST

ELECTRI	CAL	
QTY	NAME	DESCRIPTION
6251	PV MODULE	LG LG375N2W-G4 (TOTAL: 132,038 SQ. FT.)
3	PV INVERTER	SMA SUNNY CENTRAL 630CP-US 630.0 KW, 315 VAC, 1283 A
	TRANS- FORMER	1260 KVA, NEMA 3R PV-SIDE: 315 VAC, UTILITY-SIDE: 12.0 KVAC
I	TRANS- FORMER	630 KVA, NEMA 3R PV-SIDE: 315 VAC, UTILITY-SIDE: 12.0 KVAC

SITE SPECIFICATIONS EXPOSURE CATEGORY: C

RISK CATEGORY: II WIND SPEED (ASCE 7-10): 120 MPH SNOW LOAD (ASCE 7-10): O PSF

roject:

LOS ANGELES, CA 90001

roject Details:

2,344.13 kWstc, 1890.0 kW AC AHJ: LADWP

Engineering Approval:

REVIS	IONS	
DESCRIPTION	DATE	REV
	6/12/2017	A
	8/4/2017	B
Sheet Title:		
CO\	/ER	
Sheet Number:		
TI	.0	
Sheet Size: ARCH D -	36" x 24	4"
DESIGN & DRAFTING	BY:	
Sep	iSola	B K
Reviewed # Approx	rower by DE	SIGN

RD

### CONTRACTOR NOTES

- I.) THE CONTRACTOR SHALL VERIFY ALL EXISTING CONDITIONS AND NOTIFY THE SYSTEM DESIGN ENGINEER OF ANY DISCREPANCIES BETWEEN EXISTING CONDITIONS AND DRAWINGS.
- 2.) THE CONTRACTOR SHALL SUPPLY AND INSTALL ALL WORK AS SHOWN IN THE CONSTRUCTION DOCUMENTS UNLESS OTHERWISE NOTED. ALL WORK SHALL BE PERFORMED IN AN ORDERLY, WORKMAN-LIKE AND SAFE MANNER BY WORKERS SKILLED AND EXPERIENCED IN THEIR TRADES.
- 3.) THE CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATING ALL INSPECTIONS TO BE WITNESSED BY THE AHJ AND/OR THE OWNER. THE CONTRACTOR SHALL WORK WITH THE OWNER'S INSPECTION AGENCY TO PLAN THE INSPECTIONS. AND NOTIFY ALL PARTIES INVOLVED SUFFICIENTLY IN ADVANCE TO ALLOW THE INSPECTIONS TO TAKE PLACE IN A TIMELY MANNER AND NOT DELAY THE PROGRESS OF THE WORK. THE OWNER AND SYSTEM DESIGN ENGINEER WILL NOT BE RESPONSIBLE FOR SCHEDULING, ARRANGING OR COORDINATING THE INSPECTIONS.
- 4.) THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROTECTING THE AREAS WHERE WORK IS TAKING PLACE, AS WELL AS ANY ADJOINING AREAS WHICH MAY BE AFFECTED BY THE WORK, TO PREVENT SUBJECTING THE OCCUPANTS, STRUCTURES, VEHICLES, EQUIPMENT, OR ANY OTHER PARTS OR CONTENTS OF THE SITE TO HAZARD OR DAMAGE.
- 5.) CONTRACTOR SHALL FURNISH ALL NECESSARY BOXES, OUTLETS, SUPPORTS, CONDUITS, FITTINGS, AND ACCESSORIES TO FULFILL APPLICABLE CODES, REGULATIONS, BUILDING STANDARDS, AND THE BEST PRACTICE OF THE TRADE FOR THE INSTALLATION OF ELECTRICAL WORK.
- 6.) THE CONTRACTOR SHALL, AT ALL TIMES DURING THE WORK, MAINTAIN ACCESSIBILITY FROM THE STREET TO ALL FIRE HYDRANTS, POWER OR LIGHT POLES, AND SIMILAR UTILITY AND PUBLIC SERVICE ITEMS WITHIN OR ADJACENT TO THE CONSTRUCTION SITE.
- 7.) WORK SHALL NOT RESTRICT CLEAR AND UNOBSTRUCTED ACCESS TO ANY WATER OR POWER DISTRIBUITION FACILITIES (POWER POLES, PULLBOXES, TRANSFORMERS, VAULTS, PUMPS, VALVES, METERS, APPURTENANCES, ETC.) OR TO THE LOCATION OF THE HOOKUP.
- 8.) THE OWNERS AND THE AHJ SHALL BE NOTIFIED IN WRITING IN ADVANCE OF ANY REQUIRED CONSTRUCTION OPERATION THAT WILL INVOLVE INTERRUPTION OF THE HEATING, WATER, FIRE PROTECTION SYSTEMS, TELEPHONE, GAS OR ELECTRICAL SERVICES TO THE OTHER BUILDINGS AND AREAS OF THE SITE. THE CONTRACTOR SHALL COORDINATE ANY REQUIRED SHUTDOWN OF THE UTILITIES WITH THE OWNERS, THE AHJ, AND THE UTILITY COMPANY.
- 9.) UPON REVIEW OF ELECTRICAL DRAWINGS, THE ELECTRICAL CONTRACTOR SHALL INFORM THE SYSTEM DESIGN ENGINEER OF ANY DISCREPANCIES OR REQUEST CLARIFICATION, IF NECESSARY, CONCERNING THE INTENT OF THE PLANS AND SPECIFICATIONS TO PROVIDE A COMPLETE ELECTRICAL INSTALLATION.
- IO.) THE CONTRACTOR SHALL COORDINATE HIS WORK WITH OTHER CONTRACTORS WHOSE WORK MIGHT AFFECT THIS INSTALLATION. CONTRACTORS SHALL ARRANGE ALL PARTS OF THIS WORK AND EQUIPMENT IN PROPER RELATION TO THE WORK AND EQUIPMENT OF OTHERS AND WITH BUILDING CONSTRUCTION AND ARCHITECTURAL FINISH SO THAT IT WILL HARMONIZE IN SERVICE AND APPEARANCE.
- II.) THE CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATING WITH THE OWNER'S INSPECTION AGENCY TO ARRANGE FOR INSPECTIONS RELATED TO ALL SPECIAL INSPECTIONS IN A TIMELY MANNER, AND SHALL BE PRESENT AS REQUIRED AT THE INSPECTIONS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR INSURING THAT THE APPROPRIATE SUBCONTRACTORS ARE PRESENT DURING TESTS AND INSPECTIONS OF THE SYSTEMS FOR WHICH THE SUBCONTRACTORS ARE RESPONSIBLE.

### PHOTOVOLTAIC NOTES:

- I .) ALL ASPECTS OF WORK RELATED TO THE SOLAR PHOTOVOLTAIC (PV) SYSTEM SHALL BE IN ACCORDANCE WITH ALL STATE AND LOCAL CODES, UTILITY REQUIREMENTS, AND THE NEC, ESPECIALLY ARTICLE 690.
- 2.) SOLAR PV MODULE FRAMES SHALL BE BONDED TO RACKING RAIL OR BARE COPPER E.G.C. PER THE MODULE MANUFACTURER'S LISTED INSTRUCTION SHEET.
- 3.) SOLAR PV SYSTEMS SHALL BE GROUNDED IN ACCORDANCE WITH NEC 690 PART V: GROUNDING.
- 4.) COMBINER BOXES, FUSING, WIRE SIZES, QUANTITIES AND CONDUIT SIZES BETWEEN SOLAR ARRAYS AND INVERTERS TO BE VERIFIED BY CONTRACTOR WITH SOLAR MODULE AND INVERTER MANUFACTURERS BEFORE INSTALLATION.
- 5.) ALL PV SOURCE CIRCUIT CONDUCTORS AND CONNECTORS SHALL BE SUPPORTED AND SECURED WITHOUT EXCESSIVE STRESS. NO WIRING SHALL BE PERMITTED TO TOUCH THE ROOF SURFACE.
- G.) PV SOURCE CIRCUIT CONDUCTORS EXPOSED BETWEEN ARRAYS SHALL BE SECURED ON BOTH SIDES. AND BE PROTECTED FROM PHYSICAL DAMAGE AND ABRASION, INCLUDING FROM EDGES OF RACKING, CHANNEL EDGES, WIRE TRAYS, ETC.
- 7.) ANY CABLE TIES USED SHALL BE HEAT STABILIZED (-40C TO 105C), UV STABILIZED AND OUTDOOR RATED, SUITABLE AND DURABLE FOR THE ENVIRONMENT AND LIFE OF THE PV SYSTEM.
- 8.) WHERE EXPOSED TO SUNLIGHT, CONDUCTORS SHALL BE LISTED AND MARKED AS SUNLIGHT RESISTANT. 9.) ALL EQUIPMENT GROUND CONDUCTORS SMALLER THAN AWG #6 SHALL BE PROTECTED FROM PHYSICAL
- DAMAGE BY AN IDENTIFIED RACEWAY OR CABLE ARMOR UNLESS INSTALLED WITHIN THE HOLLOW SPACES OF THE FRAMING MEMBERS OF BUILDINGS OR STRUCTURES AND WHERE NOT SUBJECT TO PHYSICAL DAMAGE.

### EQUIPMENT NOTES:

- LOCATION.

- CONTRACTOR, IF NECESSARY.

- ELECTRICAL NOTES:
- BE PADLOCKED.

- SPLICED/WELDED.
- THEY WILL BE READILY VISIBLE.

I.) ALL MATERIALS, SUPPLIES, AND EQUIPMENT SHALL BE LISTED, USED, AND INSTALLED IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS AND INSTRUCTIONS, AND APPLICABLE NATIONALLY RECOGNIZED TESTING LABORATORY (NRTL) REQUIREMENTS.

2.) ALL EQUIPMENT SHALL BE RATED FOR THE ENVIRONMENT IN WHICH IT IS INSTALLED. 3.) WORKING SPACE AROUND ELECTRIAL EQUPMENT SHALL COMPLY WITH NEC 110.26.

4.) THE APPROXIMATE LOCATIONS OF ALL JUNCTION BOXES, COMBINER BOXES, CONDUITS, ETC. SHALL BE DETERMINED FROM THE DRAWINGS, AND VERIFIED BY THE CONTRACTOR FOR INSTALLATION. 5.) ALL JUNCTION BOXES, COMBINER BOXES, AND DISCONNECTS SHALL BE INSTALLED IN AN ACCESSIBLE

6.) PROVIDE NEMA 3R RATED EQUIPMENT OR BETTER WHERE EXPOSED TO OUTDOORS. 7.) WHERE SIZES OF RACEWAYS OR BOXES ARE NOT INDICATED ON THE DRAWINGS, THE CONTRACTOR SHALL SIZE THESE ITEMS AS REQUIRED FOR THE INSTALLATION.

8.) ALL VERTICAL RUNS OF CONDUIT OR TUBING TERMINATING IN THE BOTTOM OF WALL BOXES OR CABINETS OR SIMILAR LOCATIONS, SHALL BE PROTECTED FROM THE ENTRANCE OF FOREIGN MATERIAL PRIOR TO THE INSTALLATION OF CONDUCTORS.

9.) METAL RACEWAYS, METAL ENCLOSURES OF ELECTRICAL DEVICES AND EQUIPMENT, MODULE FRAMES, AND OTHER EQUIPMENT SHALL BE COMPLETELY GROUNDED IN ACCORDANCE WITH THE NEC. IO.) PROPER HARDWARE FOR A COMPLETE GROUNDING AND BONDING SYSTEM SHALL BE INSTALLED BY THE

II.) GROUNDING RODS SHALL HAVE A RESISTANCE TO GROUND OF 25 OHMS OR LESS AND SHALL BE 5/8" x 8' MIN, COPPER-BONDED STEEL. ALL GROUND CLAMPS USED SHALL BE UL 467 LISTED.

- 12.) ALL PVC CONDUIT EXPOSED TO SUNLIGHT SHALL BE SCHEDULE 80 AND MARKED AS SUNLIGHT
  - RESISTANT. ALL UNDERGROUND PVC CONDUIT SHALL BE SCHEDULE 40 OR 80.

13.) ALL CONDUIT SHALL BE MOUNTED AT A MINIMUM OF 1 INCHES ABOVE THE ROOF SURFACE.

I.) ELECTRICAL POWER MUST BE SHUT OFF PRIOR TO THE CONTRACTOR PERFORMING ANY WORK IN RACEWAYS WITH LIVE ELECTRICAL CIRCUITS OR ANY OTHER EQUIPMENT. WHEN SWITCHES OR CIRCUIT BREAKERS ARE OPENED FOR WORK ON ELECTRICAL EQUIPMENT OR WIRING, SIGNS OR TAGS SHOULD BE INSTALLED AT THE SWITCH OR BREAKER STATING THAT WORK IS BEING PERFORMED ON THEM. INCLUDE THE TIME, DATE, AND CONTRACTOR'S NAME ON THE SIGN OR TAG. IF DEVICE IS LOCKABLE, IT SHOULD

2.) THE ELECTRICAL WORK SHALL COMPLY WITH THE REQUIREMENTS OF THE AHJ, NATIONAL FIRE PROTECTION AGENCY (NFPA), NATIONAL ELECTRICAL CODE (NEC), AND OSHA.

3.) PHASING OF NEW CONDUCTORS TO MATCH EXISTING CONDUCTORS. IF INSTALLATING A NEW CIRCUIT, THEN CONTRACTOR SHALL FOLLOW THE PHASING SCHEMES PROVIDED IN THE ELECTRICAL DIAGRAM. 4.) ALL CONDUCTORS SHALL BE COPPER, RATED FOR 90°C WET ENVIRONMENT, AND 1000 VOLTS DC OR 600 VOLTS AC, UNLESS OTHERWISE NOTED.

5.) GROUNDING ELECTRODE CONDUCTOR (G.E.C.) SHALL BE CONTINUOUS AND/OR IRREVERSIBLY

6.) FLEXIBLE, FINE-STRANDED CABLES SHALL BE TERMINATED ONLY WITH TERMINALS, LUGS, DEVICES, OR CONNECTORS THAT ARE IDENTIFIED AND LISTED FOR SUCH USE PER NEC 690.3 I (F).

7.) ALL WIRES SHALL BE IDENTIFIED BY CIRCUITS IN ALL CABINETS, BOXES, WIRING TROUGHS, AND OTHER ENCLOSURES, AND AT ALL TERMINAL POINTS, I.E., RECEPTACLES, MECHANICAL LUGS, COMPRESSION FITTINGS. THE CIRCUIT DESIGNATIONS SHALL BE AS SHOWN ON THE CONTRACT DRAWINGS OR AS DIRECTED BY THE SYSTEM DESIGN ENGINEER. LABELS OR TAGS SHALL BE APPLIED TO WIRES SO THAT

8.) FUSES FOR SWITCHES SHALL BE CURRENT-LIMITING TYPE WITH A MINIMUM INTERRUPTING CAPACITY OF 200,000 AMPERES RMS (UNLESS OTHERWISE NOTED) AND OF THE CONTINUOUS CURRENT RATINGS AS INDICATED ON THE DRAWINGS OR AS RECOMMENDED BY THE MANUFACTURER.

<u><u> </u></u>	EC	CTRICAL LEGEND
	=	CIRCUIT CONDUCTORS
	=	EQUIPMENT GROUNDING CONDUCT
	=	TERMINAL BLOCK
	=	FUSE
60	=	CIRCUIT BREAKER
	=	THROW SWITCH (KNIFE-BLADE)
	=	RECLOSING CIRCUIT BREAKER
	=	RECLOSING DISCONNECT/RELAY
	=	GROUNDING ELECTRODE SYSTEM
	=	PV MODULE
	=	INVERTER
	=	MICROINVERTER
	=	POWER OPTIMIZER
	=	METER/MONITORING DEVICE
318	=	TRANSFORMER
G	=	GENERATOR
	=	TRANSFER SWITCH
	=	BATTERY
•	=	CURRENT TRANSFORMER (CT)

SITE/	/AF	RRAY PLAN LEGEND
	=	CONDUIT ROUTES
	=	CONDUIT ROUTES (UGND OR INDOORS
	=	PV MODULE
	=	PV EQUIPMENT
	=	RAFTER/TRUSS
	=	STANDING SEAM
0	=	VENT
	=	CHIMNEY
	=	SKYLIGHT
0	=	HVAC UNIT
	=	ROOF HATCH
	=	PV ATTACHMENT FLASHING
	=	RACKING RAIL
	=	SETBACKS/PATHWAYS
	=	SWINGING DOOR
$\bigcirc$	=	TREE/BUSH

### ELECTRICAL LEGEND - DC

-+

\_\_\_\_\_

G

LI

L2

L3

Ν

G

- = POSITIVE TERMINAL (PHASED RED)
- = NEGATIVE TERMINAL (PHASED BLACK)
- = GROUND TERMINAL (PHASED GREEN)

## ELECTRICAL LEGEND - AC

- = LINE I TERMINAL (PHASED BROWN)
- = LINE 2 TERMINAL (PHASED ORANGE)
- = LINE 3 TERMINAL (PHASED YELLOW)
- = NEUTRAL TERMINAL (PHASED WHITE)
- = GROUND TERMINAL (PHASED GREEN)

roject: LOS ANGELES, CA 90001 roject Details: 2,344.13 kWstc, 1890.0 kW AC AHJ: LADWP Engineering Approval:

REVISIONS DESCRIPTION DATE ORIGINAL 6/12/2017 INVERTER LOCATION 8/4/2017 Sheet Title: PROJECT NOTES Sheet Number: ΤΙ.Ι Sheet Size: ARCH D - 36" x 24" DESIGN & DRAFTING BY:

Sedisola

RD

Reviewed & Approved by:

SYMBOLL	EGEND	
SYMBOL	NAME	DESCRIPTION
	ROOFTOP PV MOD.	LG 375W
	ROOF SKYLIGHT	
0	ROOF VENT	

→ 25 ft → 50 ft → 100 ft →

SCALE: |" = 50'



554'

Project:	
LUS ANGLELS, CA SUUUT	
AHJ: LADWP	λC
Engineering Approval:	
REV/ISIONS	
DESCRIPTION     DATE       ORIGINAL     6/12/2017	REV A
INVERTER LOCATION 8/4/2017	B
Sheet Title:	
SITE PLAN	
Sheet Number: AI.O	
Sheet Size: APCHD = 2C'' + 2A	
DESIGN & DRAFTING BY:	-
SepiSola	<b>1</b>
Reviewed & Approved by:	GN
RD	

180





		Project: LOS ANGELES, CA 90001 Project Details: 2,344.13 kWstc, 1890.0 kW AC AHJ: LADWP Engineering Approval:
		REVISIONS
/- MAIN S	WITCHGEAR	DESCRIPTIONDATEREVORIGINAL6/12/2017AINVERTER LOCATION8/4/2017B
	- EXISTING UTILITY TRANSFORMER	
6		
Ω		
		ELECTRICAL
		Sheet Number:
		Sheet Size: ARCH D - 36" x 24"
		DESIGN & DRAFTING BY:
		Sepisolar.
		Reviewed & Approved by: RD





			CC	NDUCTOR S	PECIFICA	TIONS		RE	QUIRED CO	NDUCTOR AM	ΑΟΙΤΥ		AMPACITY	Y CHECK #1		CONDUCTO	OR TEMPE	RATURE DERA	ATING		CONDUIT	FILL DERATING	CORRI	ECTED AMP		ULATION	AMPACITY	CHECK #2	VOLTAGE D
TAG	CIRCUIT ORIGIN	CIRCUIT DESTINATION	MATERIAL	CONN. TEMP. RATING	RADE SIZE	AMPACITY PER 310.15(B)(16) & 310.15(B)(17)	MAX CURREN 690.8(A)(	IT X Isc (1)	# OF COMBINED = STRINGS	MAX = CURRENT PER ; 690.8(A)(1)	CONT. COPERATION 690.8(B)(1)	MAX = CURRENT PER 690.8(B)(1)	MAX CURRENT PER · 690.8(B)(1)	<pre>CONDUCTOR AMPACITY</pre>	CIRCUIT ENVIRO	NMENT LOCAL 2% AVG. HIGH TEMP (°C)	HEIGHT ABOVE ROOF (in	TEMP. ADDER PER ) 310.15(B)(3)(c	COPERATIN	D AMPACITY NG CORRECTIO C) 310.15(B)(2)(	# OF UNGROUNDE a) CONDUCTOR	AMPACITY D CORRECTION S 310.15(B)(3)(a	90°C CONDUCTO AMPACITY	R X DERATE	CONDUIT X FILL = DERATE	DERATED = CONDUCTOR AMPACITY	MAX CURRENT PER < 690.8(B)(2)	DERATED CORRECTED AMPACITY	EST. ONE-WAY DISTANCE
DC1	<b>PV STRING</b>	DCBR	COPPER	90°C AW	/G #10	55 Amps	1.25	x 10.04 >	1 :	= 12.6 Amps	× 1.25	= 15.8 Amps	15.8 Amps	< 55.0 Amps	ROOFTOP, FR	ee air 31	-	N/A	31	0.96	N/A	1.00	55	x 0.96	x 1.00 =	= 52.8 Amps	12.6 Amps <	52.8 Amps	5 ft 0.
DC2	DCBR	COMBINER BOX	COPPER	75°C <b>500</b>	) kcmil	380 Amps	1.25	x 10.04 x	24 :	= 301.2 Amps	× 1.25	= 376.5 Amps	376.5 Amps	< 380.0 Amps	ROOFTOP, IN CO	ONDUIT 31	1	22	53	0.76	2	1.00	430	x 0.76	x 1.00 =	= 326.8 Amps	301.2 Amps <	326.8 Amps	500 ft 0.
DC3	DCBR	COMBINER BOX	COPPER	75°C AW	G #4/0	230 Amps	1.25	x 10.04 >	14 :	= 175.7 Amps	× 1.25	= 219.6 Amps	219.6 Amps	< 230.0 Amps	ROOFTOP, IN CO	ONDUIT 31	1	22	53	0.76	2	1.00	260	x 0.76	x 1.00 =	= 197.6 Amps	175.7 Amps <	197.6 Amps	500 ft 0.
				CONDU	JCTOR SP	PECIFICATION	S			REQUIRED C	ONDUCTOR A	MPACITY		AMPACIT	Y CHECK #1	CONE	DUCTOR T	EMPERATURE	DERATIN	G	CONDUIT FILL I	DERATING	CORREC	CTED AMPAC		LATION	AMPACIT	Y CHECK #2	VOLTAGE D
TAG	CIRCUIT ORIGIN	CIRCUIT	ION MA	TERMI TERIAL TEM RATI	NAL IP. SI NG	ADE NUME PARA SIZE CONDU	BER OF AI ALLEL <b>31</b> JCTORS <b>3</b>	MPACITY PER 0.15(B)(16) & 10.15(B)(17)	INVERTER OUTPUT X CURRENT	# OF INVERTERS =	MAX CURRENT PER 690.8(A)(3)	CONT. X OPERATION : 690.8(B)(1)	= MAX CURRENT PER 690.8(B)(1)	MAX CURRENT PER 690.8(B)(1)	CONDUCTOR AMPACITY	CIRCUIT ENVIRC	DNMENT	LOCAL 2% E AVG. HIGH OI TEMP (°C) T	EXPECTED PERATING FEMP (°C)	AMPACITY CORRECTION 310.15(B)(2)(a)	# OF UNGROUNDED 0 CONDUCTORS 33	AMPACITY CORRECTION CO L0.15(B)(3)(a)	90°C DNDUCTOR X AMPACITY	TEMP DERATE X	CONDUIT FILL = DERATE	DERATED CORRECTED AMPACITY	MAX CURRENT PER 690.8(B)(2)	DERATED < CONDUCTOR AMPACITY	EST. ONE-WAY DISTANCE
AC1	INVERTER	TRANSFORM	AER CC	OPPER 75°	C <b>600</b>	kcmil	4	1680 Amps	1283.0 x	1 =	1283.0 Amps	x 1.25 :	= 1603.8 Amps	1603.8 Amps	< 1680 Amps	DIRECT SUNLIGH	T (+15°C)	31	46	0.82	3	1.00	1900 x	0.82 x	1.00 =	= 1558 Amps	##### Amps	< 1558.0 Amps	10 ft 0.
AC2	TRANSFORME	ER LINE SIDE CO	DNN. CC	OPPER 75°	C AWC	G #1/0	1	150 Amps	SEE XFM	IR CALCS =	101.0 Amps	x 1.25 :	= 126.3 Amps	126.3 Amps	< 150 Amps	DIRECT SUNLIGH	T (+15°C)	31	46	0.82	3	1.00	170 x	0.82 x	1.00 =	= 139.4 Amps	101.0 Amps	< 139.4 Amps	50 ft 0.

ELECTRIC SHOCK HAZARD IF GROUND FAULT IS INDICATED ALL NORMALLY GROUNDED CONDUCTORS MAY BE	SOLAR AC DISCONNECT	SOLAR DC DISCONNECT	ELECTRIC SHOCK HA TERMINALS ON THE LIN LOAD SIDES MAY BE ENE IN THE OPEN POSIT
REQ'D BY: NEC G90.5(C)       I         APPLY TO:       I         INVERTER(S), IF NOT APPLIED BY MFR	REQ'D BY: NEC 690. I 3(B) APPLY TO: AC DISCONNECT SWITCHES	REQ'D BY: NEC 690. I 3(B) APPLY TO: DC DISCONNECT SWITCHES	REQ'D BY: NEC 690.17(E) APPLY TO: DISCONNECTS, FUSES, CIRCI
GRID TIED PHOTOVOLTAIC POWER SOURCE OPERATING CURRENT: 1045 A OPERATING VOLTAGE: 740 V MAX SYSTEM VOLTAGE: 977 V	GRID TIED PHOTOVOLTAIC POWER SOURCE OPERATING CURRENT: 1035 A OPERATING VOLTAGE: 740 V MAX SYSTEM VOLTAGE: 977 V		
GRID TIED PHOTOVOLTAIC POWER SOURCE OPERATING CURRENT: 1045 A OPERATING VOLTAGE: 740 V MAX SYSTEM VOLTAGE: 977 V MAX SYSTEM CURRENT: 1380 A MAX INVERTER OUTPUT: 630 kW, 1283 A, 315 VAC	GRID TIED PHOTOVOLTAIC POWER SOURCE OPERATING CURRENT: 1035 A OPERATING VOLTAGE: 740 V MAX SYSTEM VOLTAGE: 977 V MAX SYSTEM CURRENT: 1368 A MAX INVERTER OUTPUT: 630 kW, 1283 A, 315 VAC		

) = NEW EQUIP.	(E) = EXISTING EQUIP.	LI = LINE	I (BROWN)	L2 = LINE 2 (ORANGE)	L3 = LINE 3 (YELI	LOW) N = NEUTR	RAL (WHIT
						PV Syster Local Record Low Temp: Voc Temp 25°C - Coefficient X Record +	m Maximum 2 °C Voc 1 = Correcti
						Low Temp. 0.28%/°C x 23°C +	Facto
MER-OWNED SCE-OWNED	MAIN DISCONNECT SECTION P POWER TO RELAY FROM UPS CURRENT SENSOR 5 TI 1 U U U U U U U U U U U U U U U U U U	SERVICE CABLE ERMINATION ULL SECTION	AUTOMATED PME SWITCH	TO SCE RACTOR. AND			

	16 SEC	Access Security (Serial, Ethernet)
SEL-351	25	Synchronism Check
(1) $(27)$ $(59%)$ $(81%)$	27	Undervoltage
	32	Directional Power*
	50BF	Breaker Failure Overcurrent
3	50G	Best Choice Ground
	50N	Neutral Overcurrent
	50 (P, G, Q)	Overcurrent (Phase, Ground, Neg. Seq.)
(508F) - (51g) - (32)	50/51	Adaptive Overcurrent
	51N	Neutral Time-Overcurrent
	51 (P. G. Q)	Time-Overcurrent (Phase, Ground, Neg. Seq.)
67N 50N 51N 25	52PB	Trip/Close Pushbuttons*
	59	Overvoltage
	59 (P. G. Q)	Overvoltage (Phase, Ground, Neg. Seq.)
	67N	Directional Neutral Overcurrent
52	67 (P, G, Q)	Directional Overcurrent (Phase; Ground, SEF*; Neg. Seg
	79	Autoreclosing
	81 (O, U, R)	Frequency (Over, Under, Rate)
	85 RIO	SEL MIRRORED BITS Communications*
	DFR	Event Reports
	HMI	Operator Interface
(BRM) (52PB) (DFR) (HBL) (HMI) (LGC) (LOC)	LGC	SELOGIC® Control Equations
	MET	High-Accuracy Metering
	PMU	Synchrophasors
$\left(MET\right)\left(\frac{85}{2}\right)$ (DMI) (DOM) (CED)	PQM	Voltage Sag, Swell, and Interruption*
MET RID (MU CAM SEM) (SER)	SER	Sequential Events Recorder
ine (inc	ADDITIONAL	FUNCTIONS
	BRM	Breaker Wear Monitor
	HBL	Harmonic Blocking
	LDE	Load Encroachment
t t t. t	LDP	Load Data Profiling*
χ1 χ1 χ4 χ1 or 2*	LOC	Fault Locator
	PPV	Phantom Phase Voltage
	SBM	Station Battery Monitor
Front-Panel IRIG-B EIA-232 Ethernet*1		

F	PROPOSED RELAY FUNCTIONS
DEVICE	DESCRIPTION
27-1	T/D UNDERVOLTAGE RELAY, 50%
27-2	T/D UNDERVOLTAGE RELAY, 88%
59-1	T/D OVERVOLTAGE RELAY, 110%
59-2	T/D OVERVOLTAGE RELAY, 120%
8IU-I	T/D UNDERFREQUENCY, 57 HERTZ
81U-2	T/D UNDERFREQUENCY, 58.5 HERTZ
810-1	T/D OVERFREQUENCY, 60.5 HERTZ



PHOTOVOLTAIC POWER SOURCE

REQ'D BY: CEC 690.3 | ¢ CRC R33 | .2 5 APPLY TO: JUNCTION BOXES, RACEWAYS, CABLE TRAYS, CONDUIT BODIES WITH AVAILABLE OPENINGS, EVERY 10', WITHIN 1' OF TURNS/PENETRATIONS



6 REQ'D BY: NEC 705.12(D)(3) APPLY TO: ANY/ALL ELECTRICAL PANELS CONNECTED TO MULTIPLE POWER SOURCES



REQ'D BY: NEC 690.56(C) - 7 APPLY TO: PV SYSTEM MAIN AC DISCONNECT



REQ'D BY: NEC 690.54 APPLY TO: POINT OF INTERCONNECT

				11
E)	G = GROUND (GREEN)	= POSITIVE (RED)	= NEGATIVE (BLACK)	
Voltag	e Calculation per NEC 690.7(A)	Transforme	r #1 Calculations	
D	ata Source: FULLERTON MUNICIPAL	PV Voltage: 315 VAC	Util. Voltage: 12000 VAC	
on C	orrection X Voc X Modules in = Corrected	Open Minimum Transfo	rmer kVA Rating: <b>1260.0</b> kVA	
r 1	Factor         Series         Circuit V           1.064         x         48.3         x         19         =         976.8         vol	Transforme	r #2 Calculations	
		PV Voltage: 315 VAC PV Current: 1283 Amp	s Util. Current: 34 Amps	
		Minimum Transfo	rmer kVA Rating: 630.0 kVA	
			ility-side AC System Summary	
		MAX C	URRENT PER 690.8(A): 101 Amps	
		MAX C	CURRENT PER 690.8(B): 126 Amps	Project:
				LOS ANGELES, CA 90001
				Project Details:
				2,344.13 kWstc, 1890.0 kW AC
				AHJ: LADWP
				Engineering Approval:
-				
-				
-				
-				
-				
	Inverter #1 - #3 Specif Model Number: SMA SUNN	CENTRAL 630CP-US		
	Nominal Power (kW AC): <b>630.00</b> Max A	pp. Pwr (kW AC) <b>700.00</b>		
	Max Output Current (A): <b>1283.0</b>	-)		
	CEC Weighted Efficiency: <b>98.0%</b> Maximum DC Voltage (V): <b>1000</b> Max (	Current MPPT A: <b>1350.0</b>	Array Configuration	
	DC Start Voltage (V): <b>550</b>	System:	2344.13 kWstc, 1890 kW AC al PV Module Oty: 6251	
DROP	Max. MPPT Voltage (V): <b>820</b> Min. MPPT Voltage (V): <b>500</b>		Inverter I.D. # Inv #1 Inv #2 Inv #3	REVISIONS
OLTAGE	MPPT Quantity: 1	PV F	AC Power (kW): 630.00 630.00 630.00 Power (kWstc): 783.75 783.75 776.63	ORIGINAL         6/12/2017         A
0.02%	PV Module Specificati	Invert	er DC:AC Ratio 1.24 1.24 1.23	INVERTER LOCATION 8/4/2017 B
0.03%	Model Number: LG LG37	/5N2W-G4	String Qty:         110         110         109	
0.08%	Weight (Ibs): <b>44.8</b> Dimensions (in): <b>77.2 x 39.4 x 1.8</b>	Max Open (	String Length:1919Circuit Voltage:977977	
	Power @ STC (W): 375	Min Open (	Circuit Voltage: 810 810 810	
DROP	Voc (VDC): <b>48.3</b> Vmp (VDC): <b>39.6</b> Voc Te	mp Coeff (%/°C): -0.28	rating Voltage: 740 740 740 740 740 740 740 740	
).04% ).01%	Isc (A): <b>10.04</b> Ma	x Voltage (VDC): 1,000 Max Short	Circuit Current:         1380.5         1380.5         1368.0           rating Current:         1045.0         1045.0         1035.5	
		SIGNAGE REC	QUIREMENTS	
		2.) WHITE BACK	GROUND W/ WHITE LETTERING, OK: GROUND W/ BLACK LETTERING	
	_	4.) ALL CAPITAL I	LETTERS	
IC SYST	EM	6.) WEATHER RES	BISTANT	
12 kVA		MATERIAL, FE	-R UL 969	
				Sheet Title.
				FLECTRICAL
TION				
				Sheet Number:
				E2.0
				Sheet Size:
				аксп D - 36" x 24"
				DESIGN & DRAFTING BY:
				SepiSolar
				POWER BY DESIGN
				Reviewed & Approved by:



Section using comprehensive   aintenance based on enhanced   is with optional independent   cower quality disturbances   tion (VSSI) reports.	Functional OverviewImage: colspan="2">Image: colspan="2">Image: colspan="2">Image: colspan="2">Image: colspan="2"Image: colspan="2"	ANSI Numbers/Acronyms and Functions         16 SEC       Access Security (Serial, Ethernet)         25       Synchronism Check         27       Undervoltage         32       Directional Power*         50BF       Breaker Failure Overcurrent         50N       Neutral-Ground Overcurrent         50(P,G,Q)       Overcurrent (Phase, Ground, Neg. Seq.)         51N       Neutral-Ground Time-Overcurrent         51(P,G,Q)       Overcurrent (Phase, Ground, Neg. Seq.)         52PB       Trip/Close Pushbuttons*         59 (P,N,Q)       Overcurrent (Phase, Ground, Neg. Seq.)         67N       Directional Overcurrent (Phase, Ground, SEF*; Neg. Seq.)         79       Autoreclosing         81 (O,U,R)       Frequency (Over, Under, Rate)         85 RIO       SEL MIRRORED Birs* Communications*         DFR       Event Reports         HMI       Operator Interface         LGC       SELosic* Control Equations         MET       High-Accuracy Metering         PMU       Synchrophasors         POM       Voltage Sag. Swell, and Interruption*         SER       Sequential Events Recorder         Additional Functions       BRM         BRM       Breaker Wear Monitor	Project: LOS ANGELES, CA 90001 Project Details: 2,344.13 kWstc, 1890.0 kW AC AHJ: LADWP Engineering Approval:
			REVISIONS         DESCRIPTION       DATE       REV         ORIGINAL       G/12/2017       A         INVERTER LOCATION       8/4/2017       B         INVERTER LOCATION       8/4/2017       B         INVERTER LOCATION       1       1
			Sheet Title: EQUIPMENT DATA SHEETS Sheet Number: DI.O Sheet Size: ARCH D - 36" x 24" DESIGN & DRAFTING BY:
			Reviewed & Approved by: RD